



Discount Fiberglass Pools, Inc.
8993 Tara Blvd. • Jonesboro, Georgia 30236
Office: (770) 478-2257 • Fax: (770) 477-2820
Toll Free: (800) 305-5931 • www.tallmanpools.com

ASSISTED INSTALLATION PROGRAM

EXCLUSIVE FACTORY DIRECT SAVINGS PROGRAM THAT INCLUDES:

- 1) Assisting you in choosing the perfect pool for your family.
- 2) Coordinating the delivery time of your pool with you and your excavation contractor.
- 3) A qualified representative will personally speak with your excavation contractor and go over the dig instructions prior to excavation.
- 4) Upon arrival, our employees will check the measurements of the hole and work with your excavation contractor to facilitate any necessary adjustments that need to be made. **Our employees will not operate any machinery.**
- 5) Work with your excavation contractor to assist in preparing the base of the hole with stone and installing your Water Inspection Port, Daylight Drain, or Well Point. (Additional Charges may apply for assistance with Well Points)
- 6) Prepare the pool to be off-loaded into the hole. (Equipment to off-load is not provided).
- 7) Guide the pool into the hole and work with your excavation contractor on initial leveling of the pool shell.
- 8) Place the pool equipment and run pool plumbing.
- 9) Give instructions on beginning to fill the pool with water using available water source. **(No water or start-up chemicals are provided).**
- 10) Give instructions on how and when the backfill process can be started and also how to complete it as the pool continues to fill with water. **Please note: The backfill process is a gradual one and cannot be completed until the pool is full of water.**
- 11) Temporarily connect the pump on 110v power, giving our employees the opportunity to ensure that all your equipment is working properly before they depart. **(If variable speed pump is purchased, temporary hookup will not be available).**
- 12) You will be provided with instructions on how to register for your pool warranty and access the Use and Care Manual for your pool as well as register your pool and equipment warranties. Before leaving, our employees will show you basic operations of your pool equipment. (The Use and Care Manual will be provided during the Warranty registration process).
- 13) Our crew will remain on-site until the pool has been set and you and your excavation contractor have been given instructions on how to properly do the backfill process.
- 14) Pool level should be checked with a laser transit throughout the entire installation process. **Once Tallman employees depart, maintaining the proper level of the pool shell becomes the sole responsibility of the purchaser.**
- 15) A qualified representative will personally speak with your electrician, as well as your concrete mason, to review the specifications of your project. Our office is always available to assist with any questions you or they may have.

The only contractors you will need will be an excavation contractor, an electrician, a plumber (if heater is purchased) and someone to do your pool decking. Homeowner is responsible for ensuring that each contractor contacts our office.



Discount Fiberglass Pools, Inc.
8993 Tara Blvd. • Jonesboro, Georgia 30236
Office: (770) 478-2257 • Fax: (770) 477-2820
Toll Free: (800) 305-5931 • www.tallmanpools.com

ASSISTED INSTALLATION PROGRAM

HOMEOWNER CHECKLIST:

- 1) Check with your local building department to find out if a building permit is required to install a pool and, if so, how to obtain one. We must be informed of any inspections that are required, especially any plumbing inspections.
- 2) You will need an excavation contractor to dig the hole and do the backfilling of your pool. Excavation plans can be found on our website and we will speak to your contractor to review the measurements. **We must speak with your contractor before any excavation is started.**
- 3) The day that we deliver the pool, your excavation contractor will need to be on site with equipment to make adjustments to the hole, if necessary, and to do the backfilling. **Our employees will not operate any equipment.**
- 4) You will need 40-80 tons of #89 stone (1/2" diameter) on site the day the pool is delivered. The amount of stone required depends on the pool size. No stone should be put in the hole until our installers give instructions to do so. In some cases, you may be able to use material other than the recommended stone but will need prior authorization from our office.
- 5) You will need a small crane or boom truck and four 20' straps with hooks to offload the pool. A 5-ton boom truck is usually acceptable (depending on the access).
- 6) You will need to provide water to fill the pool. We recommend using the water supply for your home but if this is not possible, you will need to hire the services of a water truck. **Please contact your sales representative for details.**
- 7) We require the installation of a Water Inspection Port. The material for this will be provided. In some instances, a "Daylight Drain" or well point may need to be installed as well as a Water Inspection Port.
- 8) You may need materials such as cinder blocks, cap blocks, 4x4's, etc. during the installation of certain models. **All materials are listed on the dig diagram for your specific model.**
- 9) You will need an electrician to hook up a 220v pump with a 20-amp breaker. **If you purchase any additional equipment such as pool light, salt system heater, etc., please discuss the additional requirements with your sales representative.**
- 10) Pool must be grounded for safety and we will need to speak with your electrician to review the electrical hook up. **Tallman Pools nor its employees will do any electrical work.**
- 11) You will need to find a contractor to do the decking around the pool. **We must speak with all hired contractors.**
 - Homeowner is responsible for pool and equipment placement, which should be free and clear of prolines and setbacks and approved by your local building department or planning and zoning office. For optimal performance, equipment should be placed no further than 25' from the pool. Notify your sales representative if your equipment will be outside of this range. Please note: A pool barrier (fence) that meets the national code will be required and is not provided by Tallman Pools. Please contact your local building permit office for more information on their specific requirements.
 - We would like to speak with every contractor that is hired and it is the responsibility of the homeowner to ensure all contractors contact our office.